



515 N. Main Street | Hinesville, GA 31313  
PO Box 649 | Hinesville, GA 31310  
912.368.5212  
www.mesack.com  
ME Sack Engineering  
@mesackengineering  
mesack



## ADDENDUM No. THREE

Date: June 19, 2024

Project: Flemington Road Improvements, MES No. 2023-80

Engineer: M.E. Sack Engineering  
Hinesville, Georgia

The original plans, specifications, and bid documents are amended to include the following:

Bid Form:

- Replace the previous Bid Form with the enclosed of the same. Note item #23 has been revised.

The following clarifications are offered for questions received:

1. *Shouldn't item #23 be per EA instead of per LF? Also, I believe that 12,700 RPM's are too many.*
  - Per GDOT detail T-15B, the RPMs are to be placed every 40 LF, which equates to 318 RPMs. We have revised item #23 to reflect a unit change to EA and a quantity of 318.

-END-

**B. BID FORM**

Bid Item	Quantity	Units	Description	Unit Price	Cost
1	35	SY	Concrete Pavement Removal	\$	\$
2	1	LS	Shoulder Scraping & Grubbing	-	\$
3	35	SY	10" Granular Roadway Base	\$	\$
4	36,165	SY	Full-Depth Roadway Reclamation	\$	\$
5	1,400	TN	Recycling Agent (Stabilization) for Base Course (Cement)	\$	\$
6	36,200	SY	1.5" Open Graded Crack Relief Interlayer	\$	\$
7	36,200	SY	2.5" 9.5mm Asphalt Paving	\$	\$
8	4	EA	Adjust Manhole Top	\$	\$
9	15	SY	Concrete Valley Gutter	\$	\$
10	1	LS	Shoulder Fill & Grading	-	\$
11	1	LS	Shoulder Grassing	-	\$
12	11	LF	24" Thermoplastic Stop Bar	\$	\$
13	280	LF	8" Thermoplastic Crosswalk Striping	\$	\$
14	635	LF	4" Thermoplastic Solid White Line Striping	\$	\$
15	270	LF	5" Thermoplastic Double Solid Yellow Line Striping	\$	\$
16	24	LF	24" Paint & Bead Stop Bar	\$	\$
17	25,465	LF	4" Paint & Bead Solid White Line Striping	\$	\$
18	6,330	LF	5" Paint & Bead Double Solid Yellow Line Striping	\$	\$
19	1,240	LF	5" Paint & Bead Dashed Yellow Line Striping	\$	\$
20	4,100	LF	5" Paint & Bead Dashed/Solid Yellow Line Striping	\$	\$
21	20,150	LF	Rumble Strips on 4" White Striping	\$	\$
22	3	EA	Transverse Rumble Strips before Stop Sign	\$	\$
23	318	EA	Raised Pavement Markers	\$	\$
24	1	LS	Traffic Control	-	\$
25	1	LS	Mobilization (5% Max)	-	\$
				<b>SUBTOTAL</b>	\$
				<b>TOTAL BID</b>	\$